



NOTE: all insulation to be HCFC free.

NOTE:
THE PERFORMANCE OF ALL PARTY WALLS RELY ON THE QUALITY OF WORKMANSHIP AND MATERIALS AND PARTICULAR ATTENTION IS DRAWN TO FULL AND PROPER COMPLIANCE WITH THE REQUIREMENTS OF BUILDING REGULATION No. 7.

THE CONTRACTOR SHALL ENSURE THAT ALL JOINTS ARE PROPERLY FILLED AND FLUSH POINTED BOTH HORIZONTALLY AND VERTICALLY.

ALL DIMS AND SIZING TO BE VERIFIED BY SPECIALIST MANUFACTURER BEFORE ORDERING/FABRICATION
CONTRACTOR TO COMPLY WITH MANUFACTURERS RECOMMENDATIONS AND INSTALLATION GUIDES
THIS DETAIL IS TO BE READ IN CONJUNCTION WITH THE WORKS SPECIFICATION NOTES

Sharon J. Ross, MBIAT.
Snr. Architectural Technologist. Mobile: 07960 152 845
Project: Station Road, Traditional construction

This document was created with Win2PDF available at <http://www.daneprairie.com>.
The unregistered version of Win2PDF is for evaluation or non-commercial use only.